

**CORRIGENDUM No. II****Sub: Creation of new Canteen facilities at Ground, 1st & 2nd floor of New Service block Bldg. NY, MDL.****Ref: MDL Tender No. 190000039 dated 08 May' 18.**

1. The following points shall be considered by the bidder(s) before submission of final offer for the subject tender.

Sl. No	Item No In BOQ	Page No.	Existing	To be read as
1	11	41	STEEL REINFORCEMENT Steel reinforcement of R.C.C work including straightening, cutting, bending, placing in position and binding all complete. Providing and fixing Thermo Mechanically treated bars of grade Fe-500D or more	STEEL REINFORCEMENT Steel reinforcement of R.C.C work including straightening, cutting, bending, placing in position and binding all complete. Providing and fixing Thermo Mechanically treated bars of grade Fe-500D or more <b><u>-For External Staircase foundation.</u></b>
2	30	45	MASONRY AND PLASTERING WORKS Providing and carrying out Pest-Control for termites, pests, white ants with final application of the chemical after completion of carpentry work. As per IS Code 6313 Part II or revisions thereof.including drilling holes at skirting level to allow the chemical to seep into walls, mixing chemical with the flooring mortar, contractor to give a certificate of Pest Treatment at the end of the job.(Measurement as per carpet area)	MASONRY AND PLASTERING WORKS Providing and carrying out Pest-Control for termites, pests, white ants with final application of the chemical after completion of carpentry work. As per IS Code 6313 Part II or revisions thereof.including drilling holes at skirting level to allow the chemical to seep into walls, mixing chemical with the flooring mortar, contractor to give a certificate of Pest Treatment at the end of the job.(Measurement as per carpet area) <b><u>-5 years warranty/Guarantee</u></b>
3	52	50	FLOORING & CLADDING WORK Providing and laying Kota stone slab flooring 25mm thick over average 20mm thick base laid over of C.M 1:4 (1 cement : 4 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing etc. complete as directed.	FLOORING & CLADDING WORK Providing and laying Kota stone slab flooring 25mm thick over average 20mm thick base laid over of C.M 1:4 (1 cement : 4 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing etc. complete as directed. <b><u>-Basic rate of kota stone 450/- Sq.mt, size 550 X 550mm</u></b>
4	53	50	FLOORING & CLADDING WORK Providing and laying Rough Kota stone slab flooring 25mm thick over average 20mm thick base laid over of C.M 1:4 (1 cement : 4 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing etc. complete as directed.	FLOORING & CLADDING WORK Providing and laying Rough Kota stone slab flooring 25mm thick over average 20mm thick base laid over of C.M 1:4 (1 cement : 4 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing etc. complete as directed. <b><u>-Basic rate of kota stone 450/- Sq.mt, size 550 X 550mm</u></b>
5	54	50	FLOORING & CLADDING WORK Kota stone slab flooring over 20 mm (average) thick base laid over steel stair steps and jointed with approved adhesive, including rubbing and polishing complete.	FLOORING & CLADDING WORK Kota stone slab flooring over 20 mm (average) thick base laid over steel stair steps and jointed with approved adhesive, including rubbing and polishing complete. <b><u>-Basic rate of kota stone 450/- Sq.mt, size 550 X 550mm</u></b>
6	63	52	FLOORING & CLADDING WORK Providing and fixing Glass mosaic tiles on finished plain wall surface of size 20 mm x 20 mm x 4 mm in all colour, design , fixing in approved design. The glass mosaic tiles shall be fixed on the wall surface with the help of approved adhesive applied at the rate of 2.5 kg per sqm and grouting of the same. All completed as per direction of Engineer-in-charge.	FLOORING & CLADDING WORK Providing and fixing Glass mosaic tiles on finished plain wall surface of size 20 mm x 20 mm x 4 mm in all colour, design , fixing in approved design. The glass mosaic tiles shall be fixed on the wall surface with the help of approved adhesive applied at the rate of 2.5 kg per sqm and grouting of the same. All completed as per direction of Engineer-in-charge.



				<b>-Basic rate of glass mosaic tiles of Rs 1455/-sq.mt</b>
7	65	53	CARPENTRY WORK Providing and fixing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length and the back side of the frame shall be painted with two coats of black japan paint and the front side of frame finished with two coats of melamine polish matching with the shutter laminate as approved etc. all complete & as directed by Engineer / Architect.	CARPENTRY WORK Providing and fixing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length and the back side of the frame shall be painted with two coats of black japan paint and the front side of frame finished with two coats of melamine polish matching with the shutter laminate as approved etc. all complete & as directed by Engineer / Architect. <b>-The wood shall be Teak wood.</b>
8	74	56	CARPENTRY WORK Providing and Fixing trap Doors for accessing the services and utilities in marine plywood 18mm thick, with necessary sized salwood framework, suspended from true ceiling bolted by anchor fasteners. Doors to be finished with laminate internally & paint on external sides, edged with PVC transparent seal to prevent smells being sucked into the trap door space. Small sized trap doors to be locked with Ellen Key locks with safety chain stays. Larger sized Doors to be divided into removable panels with notched removable framework as directed complete.	CARPENTRY WORK Providing and Fixing trap Doors for accessing the services and utilities in marine plywood 18mm thick, with necessary sized salwood framework, suspended from true ceiling bolted by anchor fasteners. Doors to be finished with laminate internally & paint on external sides, edged with PVC transparent seal to prevent smells being sucked into the trap door space. Small sized trap doors to be locked with Ellen Key locks with safety chain stays. Larger sized Doors to be divided into removable panels with notched removable framework as directed complete. <b>Ready made Trap Doors to be used</b> <b>Trap Door Technical Specs - Outer frame : 2 mm thick Aluminum powder coated</b> <b>Inner frame - 2 mm thick Aluminum powder coated</b> <b>Filler panel : Moisture Resistance board at 12.5 thick</b> <b>Locks - spring loaded locks 2 no's</b> <b>Safety string - Hi tension steel with openable grip</b>
9	80	58	PAINTING AND POLISHING WORKS Providing and applying Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	PAINTING AND POLISHING WORKS Providing and applying Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) <b>Basic rate of acrylic smooth exterior paint of Rs 150/- Sq.mt</b>
10	81	58	PAINTING AND POLISHING WORKS Providing and applying Finishing walls with textured exterior paint of required shade :New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm	PAINTING AND POLISHING WORKS Providing and applying Finishing walls with textured exterior paint of required shade :New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm <b>Basic rate of Texture paint of Rs 200/- Sq.mt.</b>
11	100	65	GENERAL ITEMS Providing & fixing 8mm Doormat of Nomad / 3M / LG Synthetic Matting system in toilet area and entrance, of approved colour and size. Etc. complete.	GENERAL ITEMS Providing & fixing 8mm Doormat of Nomad / 3M / LG Synthetic Matting system in toilet area and entrance, of approved colour and size. Etc. complete. <b>Basic rate of entrance matt of Rs 2500/- Sq.mt.</b>
12	107	66	GENERAL ITEMS Providing & fixing SS signages out of 6mm thick polycarbonate coloured back panel with 2mm thick perforated SS plate with CNC cut with necessary hardware for fitting etc. complete as directed.	GENERAL ITEMS Providing & fixing SS signages out of 6mm thick polycarbonate coloured back panel with 2mm thick perforated SS plate with CNC cut with necessary hardware for fitting etc. complete as directed. <b>- Size 150 X 450mm</b>



13	112	67	GENERAL ITEMS Providing and fixing aluminium jali with 50X25mm thick aluminium framework with aluminium mesh as per design etc. complete as per design or as directed.	GENERAL ITEMS Providing and fixing aluminium jali with 50X25mm thick aluminium framework with aluminium mesh as per design etc. complete as per design or as directed. <b>Aluminium Jali 1.5mm thk</b>
----	-----	----	---	--

2. An error has been observed in the formula incorporated in the Column 54 (Total amount with taxes) in the Price Bid (Part II). Bidders are required to note that the total amount with taxes shall be worked out by adding 18% GST over the Quoted Basic rate (Column 13 of Price Bid Part II).
3. All other terms & conditions remain unaltered.
4. The Corrigendum-II as above, duly signed & stamped, shall be scanned and submitted along with Techno-commercial Bid (PART-I) of the offer.

**Signature of Contractor**

**Seal**

**Date**