I. Modernization of Mezzanine floor, west Block, NY.

A. Dismantling of Existing:

Part: A: Existing Vigilance Office

1. Dismantling of Existing: Wooden partitions, Doors, windows, false ceiling, vitrified floor tiles, shutters at above and below window storages, cub-boards, damaged RCC, Damaged plaster, Brick work etc.

B. Providing & Fixing:

- 1. Laying of 1.0 x1.0 M Vitrified tiles with Skirting.
- 2. Granite Framing for Window.
- 3. Fixing of Aluminum Sliding window.
- 4. P & A rust removal. Rust side and PMM on damaged RCC member.
- 5. P & A internal Plaster.
- 6. P & A Bond coat on existing wall surface.
- 7. P & A up to 10mm thk. POP on internal wall surface.
- 8. P & F 35mm thk. Laminated door shutter with vision panel
- 9. P & F Door closure.
- 10.P & F Gypsum false ceiling @ periphery around the full tiles of Armstrong Ceiling.
- 11.P & A Wall & Ceiling paint.
- 12.P & F Signage's.
- 13.P & F Low Height Storages.

Etc.

II. Modernization of 1st floor, AHU area 1st floor, west Block, NY.

A. Dismantling of Existing:

Part: A: Existing Vigilance Office

1. Partition, Brick walls, Aluminum sliding windows, Damaged RCC fins etc., Damaged Plaster, Floor Tiles, Doors & Shutters, AC Foundations, Structural Steel (AC Foundations) etc.

B. Providing & Fixing:

- 1. PMM on damaged RCC members.
- 2. P & F Brick works
- 3. P & A Internal Plaster.
- 4. P & F Vitrified Tiles.
- 5. P & F Wooden/Aluminum Partition with partition with Laminate Finish.
- 6. P & F False Ceiling-Arm Strong & Gypsum.
- 7. P & F Door Shutter with Door Closures with Vision Panels.
- 8. P & F Aluminum Two Track Sliding Windows with Granite Frame.
- 9. P & A Internal Paint.

10.Etc.

Etc

III. <u>Modernization of 1st floor Vigilance Dept. West Block, NY.</u>

A. Dismantling of Existing:

Part: A: Existing Vigilance Office

1. Dismantling of Existing: Wooden partitions, Doors, windows, false ceiling, AC Ducting, vitrified floor tiles, shutters at above and below window storages, cubboards, damaged RCC, Damaged internal plaster, etc.

B. Providing & Fixing:

- 1. Laying of 1.0 x1.0 M Vitrified tiles with Skirting.
- 2. Wooden flooring for CVO cabin.
- 3. Granite Framing for Balance Window.
- 4. Fixing of Aluminum Sliding window.
- 5. P & F Kitchen Counter.
- 6. P & A rust removal. Rust side and PMM on damaged RCC member.
- 7. P & A internal Plaster.
- 8. P & A Bond coat on existing wall surface.
- 9. P & A up to 10mm thk. POP on internal wall surface.
- 10.P & F Aluminum framing with Glass Wool for Partition.
- 11.P & F 12mm Plywood with Laminate both side of aluminum partition.
- 12.P & F Glass Partition as approved in Plan.
- 13.P & F Low Height Partition.
- 14.P & F Forested Film.
- 15.P & F 35mm thk. Laminated door shutter with vision panel
- 16.P & F Door closure.
- 17.P & F Gypsum false ceiling @ periphery around the full tiles of Armstrong Ceiling.
- 18.P & A Wall & Ceiling paint.
- 19.P & F Signage's.
- 20.P & F Low Height Storages.
- 21.Etc.

Furniture Items:

- 22. Compactors-With file organizer, Chairs, Sofa set, Central Table, Side Table etc.
- 23. Executive Table along with side table & Back Unit-In veneer finish.
- 24. Anti-termite treatment.
- 25. P & F Mirror along with robe hook in each cabin

Etc.