

Scope of work: -

Name of work- Construction of Asphalt Road in Residential Area.

- 1) Earthwork in Excavation & transportation to dumping ground
- 2) Cutting of flexible pavement by mechanical means & transportation to outside MDL premises
- 3) Dismantling of PCC
- 4) Dismantling of RCC
- 5) Dismantling of Brickwork
- 6) Dismantling of Stone masonry
- 7) Taking out paver blocks
- 8) Dismantling Structural steel & shifting to MDL premises
- 9) Watering & compacting to subgrade by Vibratory roller
- 10) Providing & laying Rubble Soling, wherever required
- 11) Providing & laying WMM
- 12) Providing & applying tack coat over WMM
- 13) Providing & laying tack coat on bituminous surface
- 14) Providing & laying Dense Bituminous Surface-02layers of 50mm thick
- 15) Providing & laying Bituminous Concrete -50mm thick
- 16) Providing & laying Seal Coat 6mm thick
- 17) Providing & Applying 2.5mm thick road marking strips
- 18) Providing & laying PCC M-20grade RMC for encasing of Hume pipe
- 19) Providing & laying RCC M-35grade RMC for RCC work
- 20) Providing & laying Steel reinforcement for RCC work
- 21) Centering & Shuttering for RCC work
- 22) Providing & Laying RCC NP2 Hume pipe 250mm,300mm,450mmdia
- 23) Providing & fixing Structural Steel work for grating /covers
- 24) Providing & applying Epoxy paint
- 25) Brickwork in Plinth 230mm thick
- 26) External Plaster 20mm thick in CM 1:4
- 27) Finishing wall with Acrylic smooth exterior paint
- 28) Providing & fixing Road Studs
- 29) Providing & fixing Convex mirror
- 30) Providing & fixing pole for mirror
- 31) Raising & lowering the existing chambers to required level
- 32) Providing & laying 80mm thick CC Paver Blocks
- 33) Supplying & fixing in position GI pipe of 150mm dia.

Entire work to be executed as per Phases indicated as below:

Phase-I- All the SWD & Cross Trenches

Phase-II-Main gate to P & O terrace North

Phase-III-Currie House to P & O terrace South

Phase-IV-Main gate to Currie House Entrance & infront of Sarine House

