

ELECTRICAL SCOPE OF WORK

- The scope of work shall cover the Dismantling the existing light, fan, bell, clock, independent plug point, wiring including circuit mains of all types along with accessories etc.
- Dismantling the existing Telephone / LAN / WAN / TV cables and wires of all sizes along with casing-capping / conduit.
- Dismantling the existing Aluminium/copper mains, sub-mains wiring, all size cables etc. along with accessories etc.
- SITC of Main LT panel with 1 incomer of 250 A and 6 feeders.
- Supply, laying and termination of XLPE armoured cable from nearby Electrical Panel for incoming supply provision.
- SITC of MCCB, DBs and MCB DBs for distribution of power.
- Point wiring for light & fan points within the newly proposed Dormitory area.
- Wiring of plug points for PCs and printers in the proposed Dormitory area.
- SITC of LED panel lights, down lighters & bracket fans in the Dormitory area.
- SITC of telephone points and LAN points in the Dormitory area
- SITC of, Fire Alarm System, TV System, Rodent Repellent System.